BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51695

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/03/2022-23, Date: 21-05-2022

Name of Work:Improvements to Roads and Drains at Deshabandunagara and Surrounding areas in Ward No. 09 (Vidyaranyapura).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
1	291.06	Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)	Sqm	116.87	Rupees One Hundred Sixteen and Eighty Six Paise Only
2	430.05	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. (PWD SR 21-22 Vol -I Pg No 5 item no 1.4.1)	Cum	214.83	Rupees Two Hundred Fourteen and Eighty Three Paise Only
3	124.74	Providing granite slabs of selected quality roughly dressed having a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)	Sqm	779.10	Rupees Seven Hundred Seventy Nine and Ten Paise Only
4	56.73	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (PWD SR 2021-2022 Vol -I Pg 15 item no 2.1.3)	Cum	6643.56	Rupees Six Thousand Six Hundred Forty Three and Fifty Six Paise Only
5	111.69	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) (PWD SR 21-22 Vol -I Pg 17 item no 2.4.2)	Cum	7586.96	Rupees Seven Thousand Five Hundred Eighty Six and Ninety Six Paise Only
6	6.96	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. MORTH Specification NO.1600&2200 (PWD SR 21-22 Vol -III Pg 99 item no 13.1)	tonne	119345.00	Rupees One Hundred Nineteen Thousand Three Hundred Forty Four and Ninety Nine Paise Only
7	568.2	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2453.85	Rupees Two Thousand Four Hundred Fifty Three and Eighty Five Paise Only
8	21.6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge	Sqm	5688.90	Rupees Five Thousand Six Hundred Eighty Eight and Ninety Paise Only
9	16.17	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. 1;2;4(The cost of steel reinforcement & formwork to be paid separately) (PWD SR 2021-22 Vol -I Pg 17 item no 2.4.1)	Cum	7040.88	Rupees Seven Thousand Forty and Eighty Eight Paise Only

N. Lokanadha Reddy
Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
10	246.4	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (PWD SR 2021-22 Vol -II Pg 17 item no 6.33)	Sqm	1232.39	Rupees One Thousand Two Hundred Thirty Two and Thirty Eight Paise Only
11	430.05	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3) (PWD SR 2021-22 Vol-III Page No.3, Item No.1.1C)	Cum	81.40	Rupees Eighty One and Forty Paise Only
12	550.46	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km (PWD SR 2021-22 Vol-III Page No.3, Item No.1.4B)	t.Km	115.50	Rupees One Hundred Fifteen and Fifty Paise Only

N. Lokanadha Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92